

APPENDIX A

Proposed Scope of Work

King's Navy Yard Park Extension

To Be Completed by Amico on Behalf of the Town of Amherstburg

1. Retain the services of, and oversee the work of, Landmark Engineering to prepare the detailed construction drawings and obtain all required government approvals.
2. Prepare the final price of the works once detailed drawings are complete and confirm for the Town.
3. Prepare and enter into a CCDC fixed price contract.
4. Attempt to have government approvals "catch up" so that the work Amico is undertaking on its new mainland ferry landing can be continued to complete the work on the municipal park water's edge.
5. Complete, immediately following the receipt of government approvals, the following construction works:
 - a. Fill in front of the wall for new revetment;
 - b. Create armour stone revetment;
 - c. Grade stone;
 - d. Install filter fabric;
 - e. Cut down existing sheet pile walls;
 - f. Drive new steel sheet pile walls;
 - g. Install new railing at Sheet Pile wall along north edge (to match, as close as possible, existing Navy Yard railing);
 - h. Dredging as required;
 - i. Remove old docks and existing deadheads.